



Sample Project

Knauf Drywall

PO Box 133
Sittingbourne
Kent
ME10 3HW

Produced on 24-10-2007

This procurement schedule has been created using the facility on the Knauf Drywall website, www.knaufdrywall.co.uk. The creation of this document, the information entered and additional content and information within, is at the discretion of the person using the website facility. Knauf Drywall can not take responsibility for the adequacy of the scope of this document, which should be fully checked for completeness (eg. by a Quantity Surveyor) before any submittal.

© 2007 Knauf Drywall

2 Hour Firewall

12.5mm Knauf Fireshield 3000mm x 1200mm	37 sheets	132 m ²
52mm Knauf U-Channel 3000mm	5 lengths	12.65 m
50mm Knauf C-Studs 3000mm	27 lengths	81 m
25mm Knauf Drywall Screws	1 box	753 screws
42mm Knauf Drywall Screws	1 box	753 screws
Knauf Head/Floor Track Fixings		37 fixings
Flat Plate (Deflection)	8 lengths	22 m
Knauf Acoustic Sealant	3 cartridges	92.40 m
Knauf Joint Tape	1 roll	88 m
Knauf Joint Filler	1 bag	12 kg
Knauf Easy Sand	1 bag	16.50 kg
Knauf Wallboard Primer 2 coats	1 tub	10 litres

Note: wastage allowance is set to 10%

1/2 hour Internal

12.5mm Knauf Wallboard 2400mm x 1200mm	85 sheets	242.88 m ²
52mm Knauf U-Channel 3000mm	41 lengths	121 m
50mm Knauf C-Studs 2400mm	165 lengths	396 m
25mm Crown Wool		121.44 m ²
25mm Knauf Drywall Screws	3 boxes	2746 screws
Knauf Head/Floor Track Fixings		169 fixings
Knauf Acoustic Sealant	15 cartridges	498.96 m
Knauf Wallboard Primer 2 coats	4 tubs	37 litres
FP90	18 bags	426.11 kg

Note: wastage allowance is set to 10%

1 hour Internal

12.5mm Knauf Fireshield 2400mm x 1200mm	22 sheets	63.36 m ²
52mm Knauf U-Channel 3000mm	5 lengths	13.20 m
50mm Knauf C-Studs 2400mm	24 lengths	57.6 m
25mm Crown Wool		31.68 m ²
25mm Knauf Drywall Screws	1 box	704 screws
Knauf Head/Floor Track Fixings		44 fixings
Flat Plate (Deflection)	9 lengths	26.40 m
Knauf Acoustic Sealant	3 cartridges	84.48 m
Knauf Joint Tape	1 roll	84.48 m
Knauf Joint Filler	1 bag	11.52 kg
Knauf Easy Sand	1 bag	15.84 kg
Knauf Wallboard Primer 2 coats	1 tub	10 litres

Note: wastage allowance is set to 10%

Tall Corridor Partition

12.5mm Knauf Wallboard 2400mm x 1200mm	135 sheets	387.20 m ²
72mm Knauf U-Channel 3000mm	19 lengths	55 m
70mm Knauf C-Studs 4200mm	64 lengths	268.8 m
25mm Knauf Drywall Screws	3 boxes	2183 screws
42mm Knauf Drywall Screws	3 boxes	2183 screws
Knauf Head/Floor Track Fixings		81 fixings
Flat Plate	17 lengths	48.40 m
Knauf Acoustic Sealant	7 cartridges	224.40 m
Knauf Joint Tape	2 rolls	272.80 m
Knauf Joint Filler	2 bags	35.20 kg
Knauf Easy Sand	3 bags	48.40 kg
Knauf Wallboard Primer 2 coats	3 tubs	30 litres

Note: wastage allowance is set to 10%

Overall summary

Total number of named partitions: 4

12.5mm Knauf Fireshield 2400mm x 1200mm	22 sheets	63.36 m ²
12.5mm Knauf Fireshield 3000mm x 1200mm	37 sheets	132 m ²
12.5mm Knauf Wallboard 2400mm x 1200mm	220 sheets	630.08 m ²
52mm Knauf U-Channel 3000mm	51 lengths	146.85 m
72mm Knauf U-Channel 3000mm	19 lengths	55 m
50mm Knauf C-Studs 2400mm	189 lengths	453.6 m
50mm Knauf C-Studs 3000mm	27 lengths	81 m
70mm Knauf C-Studs 4200mm	64 lengths	268.8 m
25mm Crown Wool		153.12 m ²
25mm Knauf Drywall Screws	8 boxes	6386 screws
42mm Knauf Drywall Screws	4 boxes	2936 screws
Knauf Head/Floor Track Fixings		331 fixings
Flat Plate	34 lengths	96.8 m
Knauf Acoustic Sealant	28 cartridges	900.24 m
Knauf Joint Tape	4 rolls	445.28 m
Knauf Joint Filler	4 bags	58.72 kg
Knauf Easy Sand	5 bags	80.74 kg
Knauf Wallboard Primer 2 coats	9 tubs	87 litres
FP90	18 bags	426.11 kg

Note: wastage may vary per partition

Please check the wastage values for each individual partition above

Note: Rounding on each partition may lead to discrepancies between the two columns above on the summary page – always check each partition individually